Field	Value
Document No.	QP-024
Title	Work Transfer Control
Revision	B
Effective Date	2026-08-10
Prepared By	Owner
Approved By	Jacob Honick, Owner
Revision Approval Date	2026-11-05
Next Review	2027-08-10

QP-024 Work Transfer

Standards and clause references are guidance only and do not claim certification or standard compliance. Applicable customer, contractual and legal requirements govern accepted work.

1. Purpose

Define the process for planning, executing, and verifying transfers of work between manufacturing locations (internal or to/from subcontractors) to ensure product quality is maintained during the transition.

2. Scope

Torchworx LLC operates one shop with one owner/operator. References to a receiving source describe a possible external customer-approved supplier or a change under review; they do not establish another Torchworx LLC site or additional shop workers.

Applies to all planned or unplanned transfers of production work, including:

- Transferring work to a subcontractor (outsourcing an operation previously done in-house)
- Receiving work from a subcontractor (insourcing)
- Transferring work between facilities or equipment

3. Responsibilities

Role	Responsibility
Shop Owner	Plan work transfers, validate receiving location capability, verify product after transfer, notify customer when contractually required, maintain transfer records

4. References

- QP-003 — Purchasing and Supplier Management
- QP-022 — First Article Inspection
- QP-025 — Control of Changes
- QP-015 — Configuration Management
- AS9100 Rev D Clause 8.1 (Operational Planning and Control)

5. Definitions

- **Work Transfer:** The planned relocation of a manufacturing operation or process from one source to another (in-house to subcontractor, subcontractor to in-house, or between facilities/machines).
- **Capability Validation:** Verification that the receiving location has the equipment, tooling, personnel competence, and process controls to produce conforming product.
- **Transfer Plan:** Documentation of the transfer scope, timeline, validation steps, and acceptance criteria.

6. Procedure

Planning the Transfer

1. Identify the scope of work to be transferred: specific operations, part numbers, drawing revisions, specifications, and quality requirements.
2. Document a Transfer Plan including:
    - Reason for transfer
    - Operations/processes being transferred
    - Technical data package to be provided (drawings, specs, programs, tooling lists)
    - Capability validation requirements at the receiving location
    - Timeline and milestones
    - Customer notification requirement (yes/no and basis)

Capability Validation at Receiving Location

1. Before production begins at the receiving location, validate:
    - Equipment is capable of meeting drawing tolerances
    - The owner is competent for in-shop operations; any external supplier has the qualifications required for its customer-approved scope
    - Inspection equipment is available and calibrated
    - For subcontractors: approved on the Approved Supplier List per QP-003
2. Provide complete technical data package to the receiving location (current revision drawings, specifications, special process requirements).

Product Verification After Transfer

1. Perform full first-piece verification and full acceptance inspection by default after transfer. Complete formal FAI under QP-022 when required by the customer; use a different inspection extent only when specified or approved by the customer in writing.
2. Compare FAI results against prior production data (when available) to confirm equivalent capability.
3. If FAI fails, do not proceed to production quantities. Address root cause and re-validate.

Customer Notification

1. Notify the customer before executing the transfer when:
    - The purchase order or contract requires notification of manufacturing source changes
    - The transfer involves a special process (heat treat, plating, NDT) moving to a new supplier
    - Customer-approved process plans reference the original source
2. Document customer notification and approval (when required) in the Transfer Plan.

Records

1. Retain the Transfer Plan, capability validation evidence, and FAI results for the contract retention period.

7. Records Generated

Form No.	Title	When Completed
Transfer Plan	Work transfer planning and validation record	At initiation of each work transfer
QF-007/008/009	FAI Forms (per QP-022)	After first production at receiving location

8. Revision History

Rev	Date	Description	Approved By
A	2026-08-07	Initial release	Shop Owner

Revision B Approval

Approved 2026-11-05 by Jacob Honick, Owner. Standardize control metadata and annual review, remove fixed page counts and align applicable references and wording.